



Last updated July 2008

Millner Undergrounding

The Undergrounding Power Project started in 1997/98 when the pilot project was carried out in Nightcliff. Since then the suburb of Nightcliff has been fully undergrounded with works in Rapid Creek scheduled to be completed in December 2008.

Undergrounding work in Millner (Stage B1) commenced in March 2008 comprising of 120 properties. Works in Stages B2 and B3 which consists of 490 properties, is scheduled to commence in August 2008. Stage B1 is expected to be completed in June 2009, followed by Stages B2 and B3 in December 2009 (see map on reverse).

Stages of Works

Step 1 of the works involves directional boring under road crossings and into properties to install conduits into which the new underground cables will be placed.

Step 2 of the works involves digging a shallow trench along the nature strip. Conduits are then laid and backfilled with cement-stabilised sand. A concrete cover is laid as protection for the cables and to serve as the footpath.

Step 3 involves installing cables into the new conduits from the pillar which are then terminated at the existing meter box/supply point at each property.

Step 4 involves changing the power supply from overhead to the new underground supply.

Contact Details

Residents of Millner are encouraged to contact project staff if they have any questions or concerns regarding the Undergrounding Power Project.

Phone 1800 000 761

Email undergrounding.power@powerwater.com.au

Web powerwater.com.au



Millner Undergrounding

A Joint Northern Territory Government and Power and Water Corporation Initiative

- 
STAGE B1 - PLANNED COMPLETION
DATE JUNE 2009
- 
STAGE B2 - PLANNED COMPLETION
DATE DECEMBER 2009
- 
STAGE B3 - PLANNED COMPLETION
DATE DECEMBER 2009



MILLNER

undergrounding

Power Project