



**NOTES**

1. FOR SERVICE CONNECTION ARRANGEMENTS REFER TO S04-02-01-25 AND S04-02-01-26.
2. DRIP LOOPS SHALL BE FORMED AT EVERY INSULATION PIERCING CONNECTOR
3. ALL INSULATION PIERCING CONNECTORS SHALL BE INSTALLED BELOW THE BUNDLED CABLE.
4. EYE BOLT/NON-BREAKAWAY CONSTRUCTIONS SHALL BE USED IN THE FOLLOWING SITUATIONS:
  - WHERE THE LINE DEVIATION ANGLE BRINGS THE CABLE OVER ANY ROADWAY
  - WHERE THE CABLE CROSSES OVER ANY ROADWAY, RAILWAY OR NAVIGABLE WATERWAY.
5. NEUTRAL CORE SHALL BE BONDED TO THE POLE EARTH AT EVERY POLE.

11	1	M12 COMPRESSION LUG FOR 35SQMM COPPER CABLE	402689	S02-01-02-11
10	AR	35SQMM PVC INSULATED COPPER CABLE	1586	S02-01-01-23
9	1	INSULATION PIERCING CONNECTOR 150/35	415586	S04-01-02-15
8	1	SERVICE CROSSARM	298554	S01-01-02-11
7	1	EYE NUT	298711	S01-01-04-41
6	1	M24 X 50 BOLT	114629	S01-01-04-43
5	1	LV ABC STRAIN CLAMP TO SUIT 4 X 95 AND 4 X 150SQMM CABLE	415585	S04-01-02-11
4	4	INSULATION PIERCING CONNECTOR 185/150	415587	S04-01-02-15
3	1	M16 HOOK BOLT	197731	S04-01-02-07
2	1	SUSPENSION CLAMP TO SUIT ARIAL BUNDLE CABLE	-	S04-01-02-10
1	AR	4 X 95 OR 4 X 150SQMM LV ABC	-	S04-01-01-01
<b>ITEM</b>	<b>QTY</b>	<b>DESCRIPTION</b>	<b>ITEM No</b>	<b>DWG No.</b>

**MATERIAL SCHEDULE**

1 0	TITLEBLOCK & DRAWING NUMBER FORMATTED ISSUED FOR CONSTRUCTION	K.T. C.C.	DEC'19 APR'12	C.C. A.T.	C.C. B.C.	 NORTHERN TERRITORY	DES	A.TAYLOR	POWER STANDARD DRAWING			
							DRN	C.COPPINS	POLE TOP UNITS			
NO	DESCRIPTION	DRN	DATE	CKD	APPD		CKD	L.NIELSEN	LV ABC, BOLTED POLE CONSTRUCTION			
							APPD	A.TAYLOR	SUSPENSION ANGLE TEE-OFF			
							SCALE	N.T.S.	ROAD SIDE			
							ISSUED	APR'12	A3	DRAWING NUMBER	S04-02-01-24	
							ALL DIM. IN mm					
							DRAFTING STANDARD TO A.S.1100		CAD PRODUCT - DO NOT AMEND MANUALLY			AMDT
AMENDMENTS												