


15	1	CLAMP, DISCONNECT TEE	S01-1-4-10	2295
14	6	LUG, 35sq.mm		282277
13		Cu DROPPER CABLE, 35sq.mm PE/PVC, (19/1.53, 17mmDIA)	S2-1-1-5	9092
12	2	CLAMP LIVE LINE	S1-1-4-17	2139
11	2	CLAMP, ALUMINIUM BAIL	S1-1-4-10	5603
10	3	SHACKLE STRAP	S1-1-4-5	9183
9	3	BOLT M24 50 LONG CW NUT		
8	3	BALL HOOK, LONG SHANK	S1-1-4-2	3111
7	9	SUSPENSION INSULATOR (including security clip)	S1-1-3-2	3012
6	3	SOCKET TONGUE	S1-1-4-3	3087
5	3	THIMBLE CLEVIS	S1-1-4-3	6767
4	3	PREFORMED DEADEND	S1-1-4-18
3	-	CONDUCTOR 3/2.75 SC/AC OR 3/4/2.50ACSR/GZ		
2	1	CROSSARM STEEL RURAL TERMINATION	S1-1-2-2	9605
1	1	13.5C POLE	S1-1-1-2	11122

1	ITEM 15 ADDED, ITEMS 11, 12 AND 14 QUANTITY CHANGED. APPROVED FOR CONSTRUCTION.	RCI	SEP'99	MWB	FRR
NO	DESCRIPTION	DRN	DATE	CKD	APPD
AMENDMENTS					



DES	M. BOCK	POWER STANDARD DRAWING		
DRN	R. INNES	SINGLE WIRE EARTH RETURN ISOLATING TRANSFORMER POLE TERMINATION ASSEMBLY		
CKD	S. SAWYER			
APPD	F. ROBSON			
SCALE	1:20			
ISSUED	23/10/97			
ALL DIM. IN mm	A3	DRAWING NUMBER	S25-2-1-02	
DRAFTING STANDARD TO A.S.1100		CAD PRODUCT - DO NOT AMMEND MANUALLY		